OFFICE OF THE PRESIDENT, TOWN MUNICIPAL COUNCIL, CHINTAMANI.

Notice dated the 7th November 1935.

Sealed tenders will be received at the Office of the President, Town Municipal Council, Chintamani, up to 3 P.M. on 29th instant for constructing the Municipal Office, Chintamani.

Each tender must be accompanied by a deposit of Rs. 500 in cash or currency notes as earnest money and be superscribed "Tender for constructing the Municipal Office, Chintamani," in default of which tenders will be rejected.

The work should be completed by the end of March 1936.

The plan and detailed estimate and conditions may be seen at the Municipal Office, Chintamani, during the office hours on working days. The quantities noted below are not guaranteed. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

The final acceptance of the tender will rest with the President who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Municipal Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Charges on account of materials, implements for setting out, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

In all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the President will be final and legally binding.

Abstract estimate for constructing the Municipal Office Building at Chintamani.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavation for foundation ...	Cyd.		220	
2	Concrete with burnt stone jelly and chunam for filling in foundation.	C.ft.		1,475	
3	Burnt size stone in mortar for filling foundation and basement.	,,		4,645	
4	Burnt brick in mud for superstructure ...	,,		3,809	
5	Do in mortar do ...	,,		2,126	
6	Burnt stone slabs 6″ thick exposed portions single line dressed and fixed in mortar.	S.ft.		2,756	
7	Plastering with chunam mortar ...	Sqr.		87·84	
8	Whitewashing two coats ...	,,		87·84	
9	Teakwood doors panneled shutters with necessary bolts, hinges and locking arrangement, etc., complete.	S.ft.		442	
10	Teakwood windows panneled shutters outside and glazed shutters inside with iron bars, hinges, etc., complete.	,,		336	
11	Teakwood glazed ventilators with iron bars, etc., complete.	,,		96	
12	Cut stone circular pillars 10′ high and 1½′ in diameter with base and capital including three line dressing.	C.ft.		197	
13	Rolled steel girders including hoisting and fixing and painting.	Cwt.		28	
14	Roofing with reinforced hollow bricks including 3″ concrete, plastering and ceiling, etc., complete.	Sqr.		20·83	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
15	Teakwood work wrought and put up complete with wood oiling.	C.ft.		134	
16	Steel stresses for roofing of hall for a span of 24 feet including hoisting, fixing and painting, etc., complete.	No.		3	
17	Roofing with 1st class Mangalore tiles on teak reepers including reepers wood oiling.	Sqr.		16·56	
18	Teekwood eve Board 9″ wide plain including fixing, etc., complete.	R.ft.		152	
19	Ceiling with soft wall board including fixing, etc., complete.	Sqr.		10·40	
20	Ridge tiles plain set in cement mortar ...	R.ft.		112	
21	Flooring with 3″ chunam concrete and 1st class Mangalore tiles laid diagonally with border including cement painting.	Sqr.		19·92	
22	Flooring with 3″ chunam concrete and Cuddapah slabs including cement pointing.	Sqr.		4·80	
23	Burnt brick in mortar plain cornice 1′ thick including plastering.	R.ft.		398	
24	Burnt brick in mortar plain parapet wall 2′ high including plastering, etc., complete	R.ft.		398	
25	Teak wood ornamental frame work 2½′ high in the verandah including fixing and painting.	R.ft.		19	
26	Selicate painting 2 coats to doors and windows.	Sqr.		19·90	
27	Pointing with cement portar stone basement	Sqr.		4·96	

R. VARADARAJ PILLAY,
President.

CHIKBALLAPUR SUB-DIVISION.

Notification No. S4. C. 400—35-36, dated 7th November 1935.

Under Section 17 of the Mysore Village Panchayet Regulation, Mr. Shanbhog Lakshminarasappa of Kariappalli village, is declared as elected Village Panchayet Member of Kodigallu Village Panchayet, Chintamani Taluk, *vice* Mr. Shanbhog Khadreppa, deceased.

M. ISMAIL SHERIFF,
Assistant Commissioner.

TUMKUR DISTRICT.

Notification dated 25th October 1935.

Right of collecting fees on cattle and shops and of collecting manure during the ensuing Jatra of Sri Subrahmanyaswami of Nagalmadike (to come off on 31st December 1935 for a week).

1. The right to collect fees on cattle and shops and to collect manure at the ensuing Jatra of Sri Subrahmanyaswami at Nagalmadike during the year 1935-36, will be sold by public auction by the Assistant Commissioner and Madhugiri Sub-Division Officer on 8th December 1935 at the Pavagada Taluk Office.

2. Persons intending to bid at the sale must attend in person or by a duly constituted agent.

3. The sale will be subject to the following conditions :—

1. The purchaser of the contract shall collect fees at the rate of two annas on every head of cattle and one anna on each head of calf and on shops at the rates specified in the schedule given below.